



महावीर वात्सल्य अस्पताल

(महावीर मंदिर, पटना द्वारा संचालित)

एल. सी. टी घाट, पटना - 800 001

सदाकत आश्रम से पूर्व, पटना - 800 001, दूरभाष : 9473367537

पत्रांक : MVA/310/2025

दिनांक 30/05/2025

Quotation Invitation

Quotation are invited in sealed cover envelope by 2th June 2025 for 10 KL LMO Civil and other related construction work for new 10 KL LMO Plant civil work for installation for Mahavir vaatsalya Asptal , LCT Ghat Patna-800001

s.no	Mahavir Vaatsalya Asptal LCT Ghat Patna	Area	Quote Rate
1.	All types of civil work RCC Foundation , Brick work , grill mesh work and demolishing old rcc and Brick structure all related job of this civil construction work	BOQ measurement work detail list has to attached at 2 pages	

7/8041
(M.P. Sinha)

Assistant Director
Mahavir Vaatsalya Asptal

ESTIMATE FOR CIVIL WORK TOTAL WORKING COST OF LMO 10 KL IS = 5,69,255/-			
FOR INSTALLATION OF TANK CIVIL WORK WITH EXISTING STRUCTURE DEMOLITION WORK			
AS PER PARTICULAR TOTAL WORK BOQ SHEET			
(A) MATERIAL REQUIRMENT QUANTITY			
S. NO	Particular work description and material description name & work name	Matrrial Qty & Measurment	(Rs) Amount
1	Cement psc Altratech	189 bags	
2	Sone sand	500 cft	
3	Stone chips (5/8)	741 cft	
4	brickl no	4382 pcs	
5	Ganga sand	210 cft	
6	steel 12 mm	29 pcs	
7	steel 10 mm	12 pcs	
8	steel 8 mm	80 pcs	
9	Fire 4 pcs bkt set with stand	1 set	
(B) LABOUR WORK QTY DETIAL			
	Work name Details	WORK QTY	
10	soil excavation & De watering	3135 cft	
11	Ganga Sand filling	163cft	
12	Brick Soiling	293cft	
13	pcc work	100cft	
14	Rcc + suttering & desuttering	773cft	
15	steel cutting & binding work	778 kg	
16	Soil filling work	1406 cft	
17	Brick masonry work	463 sft	
18	Plaster work	146 sft	
19	Grill mesh fencing work and supply	78 sft	
20	Barrier post fitting concreting work	4 nos	
21	Main Gate welding with fitting concreting	2 sets	

May
29/05/25

O. Jayanti
28/5/2025

FOR INSTALLATION OF TANK CIVIL WORK WITH EXISTING STRUCTURE DEMOLITION WORK
(C) Demolishing Dismantalling and Disposal work cost

22	As per particular work detail BOQ has calculated	
	Particulars Details	Work measurement Qty
23	Total RCC structure demolishing	336 cft
24	Brick wall demolishing and stacking and lead ahead	188 cft
25	Mortar unused removing from B/w wall	188 cft
26	Disposal and transpoting unservisable waste material malba and garbages	470 cft
27	Dismantalling of window 3 units of difference size - 7'x4' , 4'x5' , 4.5'x 5'	3 units
28	Dismantalling of Grill mess gate has 2 units size- 16'5"x 6'	2 units
29	Grill mesh fencing grill dismantalling work sizes 5'x 6'	2 units
30	Dismantalling of Door sizes 7'x 3'	1 unit

Total working costing approx Amount = 5,69,255/-

[Signature]
29/05/25

[Signature]
28/5/2025